



टीकापुर नगरपालिका नगर कार्यपालिकाको कार्यालय

फोन नं. { ०९१-५६०४९९
०९१-५६१२५४
०९१-५६०११८

प.सं. : २०८२।८३

च.नं. : ३५८८




दरभाउपत्र पेश गर्ने सम्बन्धी सूचना

दोस्रो पटक प्रकाशित मिति:- २०८३।०१।२४

१. टीकापुर नगरपालिकाको स्वीकृत वार्षिक कार्यक्रम अनुसार तपसिल बमोजिमको कार्य खुला दरभाउपत्र मार्फत गर्नु पर्ने भएकाले ईच्छुक निर्माण व्यवसायीले यो सूचना प्रकाशित भएको मितिले ७ दिन भित्र दरभाउपत्र टीकापुर नगरपालिका, नगर कार्यपालिकाको कार्यालयमा पेश गर्नहुन यो सूचना प्रकाशित गरिएको छ।

क्र.सं.	कामको विवरण	लागत अनुमान रकम	दर-भाउ पेश गर्ने अन्तिम समय	कैफियत
१	वडा न.९ को अधुरो भवन निर्माण	५,८४,३४०.४० (मु.अ.कर समेत)	मिति २०८३।०१।३० (कार्यालय समय भित्र)	
२	टीकापुर नगरपालिका वडा न. ०२ का विभिन्न सडकहरु मर्मत सम्भार	५,९९,६६५.४६ (मु.अ.कर समेत)	मिति २०८३।०१।३० (कार्यालय समय भित्र)	

२. दरभाउपत्र पेश गर्ने निर्माण व्यवसायीले अनिवार्य रूपमा दरभाउपत्र पेश गर्ने व्यहोरा सम्बन्धको लिखित निवेदन सहित नविकरण भएको फर्म/कम्पनी दर्ता प्रमाण पत्रको प्रतिलिपी, मु.अ.कर दर्ता प्रमाण पत्रको प्रतिलिपी, नविकरण भएको निर्माण व्यवसायी ईजाजतपत्रको प्रतिलिपी, चालु आ.व.को लागी टीकापुर नगरपालिकामा सुचिकृत भएको निस्साको प्रतिलिपी र आ.व. २०८१/०८२ को करचुक्ता प्रमाणपत्रको प्रतिलिपी संलग्न गरी पेश गर्नुपर्ने छ।
३. उक्त कार्यको लागि आवश्यक BOQ यस कार्यालयको वेबसाइट <http://www.tikapurmun.gov.np> बाट डाउनलोड गर्न सकिनेछ।
४. BOQ मा आफुले कवोल गरेको रकम अंक र अक्षरमा स्पष्ट बुझिने गरी लेखेर पेश गर्नु पर्नेछ। केरमेट भएको दरभाउपत्र (BOQ) मुल्याङ्कनमा समावेश गरिने छैन।
५. प्रस्तावदाताहरुले दरभाउपत्र सार्वजनिक खरिद नियमावली, २०६४ को नियम ८५ को उपनियम १(ख) बमोजिम उल्लेखित सिमा (दश लाख) भित्र रही पेश गर्नु पर्नेछ।
६. दरभाउपत्र पेश गर्ने अन्तिम दिन सार्वजनिक विदा पर्न गएमा सो दिनको भोली पल्ट कार्यालय समयभित्र दरभाउपत्र पेश गर्न सकिनेछ।
७. म्याद नाधी आएको, रित नपुगेको वा कुनै शर्त राखी पेश गरेको दरभाउपत्र मान्य हुने छैन।
८. माथि उल्लेखित बाहेक प्रचलित ऐन कानून बमोजिम हुनेछ।


राजेन्द्र रावल

नि.प्रमुख प्रशासकीय अधिकृत

नि.प्रमुख प्रशासकीय अधिकृत

वेबसाईट : www.tikapurmun.gov.np

सम्पर्क नं. : सा.प्रशासन शाखा ०९१- ५६०८१६

श.पु.तथा वि.शाखा ०९१- ५६१३२५

ईमेल : tikapurmun@gmail.com

सा.ख.तथा स.व्य.उपशाखा ०९१- ५६०८८३

वारुणयन्त्र ०९१-५६०४९९



Tikapur Municipality
Office Of Municipal Executives
Sudurpaschim Province
Tikapur, Kailali

Bill of Quantities (BOQ)

Name of Project :- वडा नं.९ को अधुनो भवन निर्माण
Location:- Tikapur Municipality-9, Jhuga, Kailali
F/Year :- 2082/ 083



प्रमुख प्रशासकीय अधिकारी

Item No.	Description	Quantity	Unit	Rate excluding VAT		Amount Rs	Remarks
				In Digit	In Words		
A	Provisional Sum						
1.0	Project Information Bord (Suchana Pati Preparation and Installation Works)	1.00	Job	3500.00	Three Thousand Five Hundred only.	3500.00	
B	Civil Works						
1.0	First class chimney made Brick work (1:4) in sub - structure in ground floor & Other Floor in cement sand mortar with approved quality bricks in perfect line & level with necessary scaffolding including wetting the bricks, properly packing the joints & curing the works with all complete as per instruction of site incharge/ engineer on the basis of drawings, specifications, etc.	8.81	M3				



Tikapur Municipality
Office Of Municipal Executives
Sudurpaschim Province
Tikapur, Kailali

Bill of Quantities (BOQ)

Muc
इन्जिनियर

Name of Project :- वडा नं.९ को अधुरो भवन निर्माण
Location:- Tikapur Municipality-9, Jhuga, Kailali

F/Year :- 2082/ 083



Prasad
प्रसाद प्रशासकिय अधिकृत

Item No.	Description	Quantity	Unit	Rate excluding VAT		Amount Rs	Remarks
				In Digit	In Words		
2.0	PCC for RCC Works : Providing, laying, compacting and curing M20 (1:1.5:3) plain cement concrete for slab, columns, beams, tie beam Lintel Sill Fins and all kinds of R.C.C. works with cement sand and crushed aggregate of required size finishing to approved level, line and dimensions all complete using concrete mixture and compaction with vibrator including formworks as per specifications, drawings and instructions of the site engineer, all complete.	0.70	M3				
3.0	12.5mm Plaster Work Providing and laying cement mortar 1:4 (1 cement : 4 coarse sand) With finishing work curing, and all complete as per drawing, specifications and instructions of the Engineer.	764.81	M2				



Tikapur Municipality
Office Of Municipal Executives
Sudurpashchim Province
Tikapur, kailali
Bill of Quantities (BOQ)



[Signature]
प्रमुख प्रशासकीय अधिकृत

नामः Project :- वडा नं.९ को अग्ररो भवन निर्माण
Location:- Tikapur Municipality-9, Jhuga, Kailali
F/Year :- 2082/ 083

Item No.	Description	Quantity	Unit	Rate excluding VAT		Amount Rs	Remarks
				In Digit	In Words		
4.0	3 mm Cement Punning Works in all 1st Floor Bulidig area	117.57	M2				
5.0	18" Indian pattern(ISI) With all complete set.	1.00	Set				
6.0	110mm PVC pipe of 4kg/cm2 (6 m long)	3.00	Nos				
7.0	4" PVC Bend Using in Toilet	1.00	Nos				
8.0	75mm PVC pipe of 4kg/cm3 (6 meter long)	5.00	Nos				
9.0	3" PVC Tee	1.00	Nos				
10.0	3" PVC Bend Type	3.00	Nos				
11.0	Wash Basin 20"*16" (Good) With all Complete Work.	1.00	Nos				



M. P. Singh
इतिहासिक

Tikapur Municipality
Office Of Municipal Executives
Sudurpashchim Province
Tikapur, kailali

Bill of Quantities (BOQ)

Name of Project :- वडा नं.९ को अशुद्ध भवन निर्माण
Location :- Tikapur Municipality-9, Jhuga, Kailali
F/Year :- 2082/ 083



P. P. Singh
प्रमुख प्रशासकीय अधिकारी

Item No.	Description	Quantity	Unit	Rate excluding VAT		Amount Rs	Remarks
				In Digit	In Words		
12.0	3/4 inches CPVC Pipe	6.00	Nos				
13.0	2x2.50 sq mm multi strand flexible CU wire for light & fan point in 1/2" HDPE polythene pipe etc all complete.	20.00	Point				
Total							
13% VAT							
Total Amount with VAT							

In Words:
Company's Name :-
Name of Contractor :-
Address :-
Phone No :-
Date :-

Company's seal :-
Contractor's Signature :-
Mobile :-
Fax :-
E-mail :-